

LOGO.S with steel facing

PRODUCT INFORMATION





LOGO.S with steel facing

Compact formwork panel with integrated accessories

The LOGO.S formwork system is a well-conceived complete unit, since all the necessary accessories are integrated on the formwork panel so that they are foldable or mountable.

In addition to a concrete pressure capacity of up to 100 kN/m², the LOGO.S wall formwork also boasts full compatibility with the LOGO series.

Benefits

- Panel with integrated folding working platforms and accessories
- Time saving during assembly
- Perfect concrete finish
- Continuous height offsetting of the panels due to clamp connections
- Formwork with precision down to the centimetre thanks to full compatibility with the LOGO range



The crane lifting clamp is a core component of all formwork panels in the LOGO.S system.

Intelligently planned down to the last detail

All LOGO.S formwork panels are equipped with "Multip" an integrated, foldable working platform, and combined with all the required accessories to form a complete unit:

- · Working platform with lateral protection · crane lifting clamp for upright transport
- · Adjustable prop and support
- Front protection

- · lifting lugs for horizontal transport
- · Mounting for wedge clamp
- · Mounting for tie rods + ball joint plates

All accessories are always on the panel and do not have to be searched for or fetched over long distances. In addition, formwork panels and accessories can always be moved together and stored in a space-saving way. This saves time and money!




In addition to the basic panel measuring 240 x 270 cm, there is a midi panel measuring 135 x 270 cm and pass panels measuring 90/60/30 cm in width. These panels are also equipped with safety devices. Due to the unlimited compatibility of the LOGO system components, all concrete constructions can be formed with centimetre accuracy without having to create custom-made pieces on site.

Perfect concrete finish and at the same time reduced number of tie points

For wall heights of up to 265 cm, only one tie point remains in the concrete, as an additional anchoring option at the top end of the panel allows clamping above the concrete. This corresponds to just 0.3 ties/m² in the concrete.

The durable steel formwork skin is welded flush from the frame side so that neither screw/rivet marks nor frame marks remain in the concrete and excellent exposed concrete results are achieved.



The panels are a compact unit when folded, with the "Multip" safety device firmly attached together with all other accessories.



Well thought-out down to the last detail: for a tidy construction site without material loss.

